CONCEPT DESIGN REPORT

WADJEMUP MODULAR WAVE APARTMENTS




CONTENTS

CONCEPT	2-3
MODULE CONNECTIONS	4
reconfiguration	5
Innovation and research	6
net zero considerations	7
BUILDING COMPLIANCE - NCC	8
SERVICES	9
Engineers report	10-11









WADJEMUP / ROTTNEST ISLAND, WESTERN AUSTRALIA

CONCEPT





CONCEPT SITE RESPONSE

DESIGN SYNERGY (Bridled tern) Summer scented wattle Wadjemup Teatree (using endemic plants) (Quokka) (Wadjemup Pine tree) Birin-Birin (Rain bow Bee-Eater) Coastal Bush Daisy Dek-koordiny-mart (Wadjemup daisy) (Crow) Hardenbergia climbing plant Kangaroo Paw

ENVIRONMENT AND COMMUNITY

Coastal Erosion Hotspot Area

The sites are located with an ared where coastal erosion is highly likely to impact on public and private physical assets and require management and adaptation action within 25 years. (DPLH. 2019. Coastal Erosion Hotspots in Western Australia.)

Wadjemup is a Class A reserve

The RIA Rottnest Island Authority has a strong focus on preserving its natural environment and rehabilitating its biodieristy. The site is surrounded by tall trees that provide a soft eclsure to the spaces and provide shade to the north and south of the plot.

THE WAVE FORM OF THE MODULAR HOUSING IS INSPIRED BY THE UNIQUE VIEWS OF THE OCEAN AND THE TOPOGRAPHY OF THE ISLAND. THE DESIGN IS INTEGRATED WITHIN ITS SURROUNDINGS TO DEMONSTRATE HOW MODULAR DESIGN DOESN'T HAVE TO BE BOXES LACKING IN CHARACTER



DESIGN DRIVERS

1. CONNECTION WITH UNIQUE SITE

PROTECT NATURAL

ENVIRONMENT

The design creates direct vi sual connection with the site rees and native vegetation the site.

Integrating the colours and textures present on the istextures present on the 1s-land and local sites inco the material palette. And shaping the building form around the trees on the site to immerse them with views

Morphing the shape of the nousing on the second site with the shape of the dune o connect with the site and illow for maximised views of the unique ocean site.


ottnest Island council to Rothest Island council to protect its natural environ ment and ecosystems to take care for the place and to restore its biodiversity Restoring the ecosystem of the dunes if important to revent erosion. Protecting he trees on the site is the nost effective design solu ion for sustainability, bein

The practice of living with the ecological systems of the land is practice that the Custodians of the land - the


COMMUNITY SPACES


MODULE CONNECTIONS


Designed for disassembly and maximised configurations through simple modules size 8m x 3.5m using a Glue Laminated Timber (GLT) structural interlocking system and prefabricated Rippman floor/ceiling panels (RFS), and hemp-lime walls.





GLUE LAMINATED TIMBER MODULE STRUCTURAL SYSTEM













RECONFIGURATION



500M DISTANCE BETWEEN SITE 1 AND 2 TRANSPORT MODULES BY TRUCK AND CRANE TO SITE 2 FOR RECONFIGURATION







INNOVATION AND RESEARCH

MATERIALITY



- GLUE LAMINATED TIMBER (GLT) STRUCTURE
- + Low carbon building material
- + 3x stronger than steel
- + Healthy building material
- +100+ year life expectancy
- + Reusable after deconstruction



RIPPMAN FLOORING SYSTEM (RFS)

- + Lower embodied carbon per m2 than typical slabs or steel & CLT systems
- + 3D printed or cast system to fit module sizes
- + Strength through its patterns requires no
- + Biomorphic patterns benefit user wellbeing



HEMPCRETE BIOCOMPOSITE WALLS

- + Made with Hemp hurd, Lime binder, water
- + Carbon negative material
- + 7x stronger and 3x more elastic than concrete
- + Thermally insulative
- + Non combustible
- + Water proof
- + Acoustic insulation





RECYLED TIMBER FLOORING

- + Recyclable in full form
- + 40+ Yrs life capacity
- + Thermally efficient material
- + Timber improves mental wellbeing







TIMBER SCREENS & STEAM BENT SHADES

- + Fire resistant BAL 12.5,15,19 and 29
- + 40+ years life span
- + BCA C1.10a satisfied
- + Low embodied energy in production
- + Sustainable forestry
- + Timber improves mental wellbeing



NATIVE GARDEN ROOFS

- + Collects water
- + Cools the building
- + Reduces urban heat island
- + Increases biodiveristy
- + Improves human health





SCALLOPED CERAMIC FACADE TILES

- + Local buildings are white/cream
- + Soft white to mimic sand
- + Shape mimics coastline rock shapes
- + One of the most sustainable cladding
- + Acoustic insulation
- + Thermal insulation
- + Non combustible.






WESTERN RED CEDAR FRAMES

- + More thermal efficiency than aluminium
- + Low conductivity prevents solar heat gain
- + Sustainable forestry



NET ZERO CONSIDERATIONS


REDUCING ENERGY CONSUMPTION & CREATING NEW RECOURSES



LOW CARBON AND CARBON NEGATIVE BUILDING MATERIALS



REDUCE GLARE & EXCESS HEAT GAIN WITH TIMBER SCREEN FACADE



HEAT RECOVERY AIR SYSTEM




SAVING TREES TO SEQUESTER CARBON & PRODUCE OXYGEN




THERMAL COMFORT WITH HEMPCRETE WALLS & ROCKWOOL INSULATION




RAINWATER COLLECTION & PERMEABLE URBAN SURFACES



PASSIVE COOLING WITH CROSS VENTILATION & GARDENS



PASSIVE DAYLIGHT FOR THERMAL COMFORT, & SOLAR ENERGY



COMMUNAL SPACES AND APARTMENTS CONNECTED TO NATURE

BUILDING COMPLIANCE

SECTION A | A6 Building Classification

Peddle and Flipper Ground floor: Class 2 Floor 1 - 3 apartments: Class 6

SECTION B | B1 Structure Classification

Class A - 6A

A Class 6 building is a shop or other building used for the sale of goods by retail or the supply of services direct to the public

SECTION C | Fire Resistance

The building requires professional certification from a certified fire engineer to ensure it meets the safety needs. The building safeguards people from illness or injury due to a fire in a building with access to fire isolated stairs and lifts with sufficient exits. The Hempcrete walls avoid the spread of fire between buildings due to their non-combustible quality and BAL 40 rating.

SECTION D | Access and Egress / Provision for Escape / Construction of Exits / Universal Access

The building provides people with safe, equitable and dignified access to the services and facilities within a building; and safeguards occupants from illness or injury while evacuating in an emergency.

D1P1 Access for people with a disability

Access is provided to approach the building from the road boundary and approach the building from any accessible associated building. There is access to work and public spaces, accommodation and bathrooms; with easy identification of accessways.

• D1P2 Safe movement to and within a building

All walking surfaces have safe flat gradients, all stairs have handrails and slip-resistant surfaces, the stairs have suitable landings to avoid fatigue.

D1P3 Fall prevention barriers

Barriers are provided where people could fall at a height of 1 m or more and are constructed to prevent falling through.

• D2D3 Number of exits required

The building has 2 exits from every level, and multiple exits on the ground floor.

D2D5 Exit travel distance

The Class 2 building has entrance doorways to sole-occupancy units within 6 m from an exit or from a point from which travel in different directions to 2 exits is available; or 20 m from a single exit serving the storey at the level of egress to a road or open space.

SECTION E | Fire-fighting equipment

The building is rated BAL 12. It is to be provided with fire-fighting equipment to safeguard against fire spread to allow occupants time to evacuate safely without being overcome by the effects of fire; and so that occupants may undertake initial attack on a fire; and so that the fire brigade have the necessary equipment to undertake search, rescue and fire-fighting operations.











SECTION F | F3 Rooms heights / F4 light and ventilation / F5 Sound transmission

The building safeguard occupants from injury, illness or loss of amenity due as it allows for constant connection with natural light, with artificial lighting when necessary; all living spaces have access to fresh air through windows and timber screens in walkways to safeguard occupants from illness or loss of amenity. All apartments have insulative materials to reduce sound transmission such as the hempcrete walls and uses of timber for acoustics.

F6P1Natural lighting

Sufficient openings must be provided and distributed in a building, appropriate to the function or use of that part of the building so that natural light, when available, provides an average daylight factor of not less than 2%.

• F6P3 Outdoor air supply


The spaces used by occupants are provided with means of ventilation through operable windows to maintain adequate air quality. The building has and maintains native gardens to improve air quality.

F6D7 Natural ventilation


All living spaces have openings, windows, doors to ventilate the rooms. The apartments all have access to open verandahs adjoining living rooms and a large communal open garden space.

SECTION J1 | Energy efficiency


The building reduces energy consumption and energy peak demand with passive daylighting, and reduces greenhouse gas emissions with thermal insulation with highly effective materials such as timber and hempcrete with insulation to prevent excess heat gain and loss, allowing for user comfort to improve occupant health and amenity.




SERVICES



APARTMENT SERVICES CONNECTION (PLAN DETAIL)



BUILDING SERVICES SHAFTS (FIRST FLOOR PLAN)



2 BEDROOM 1 BATHROOM MODULAR APARTMENT TYPE

ENGINEERS REPORT

DETAILED COSTING ESTIMATE

Sumi	mary			
Schedule No. 1 - WORK UNDER CONTRACT				
CLASS A4 - PROVISIONAL SUMS	\$	42,812.00		
CLASS A - GENERAL ITEMS	\$	509,734.72	\$	552,546.72
CLASS B - GROUND INVESTIGATION			\$	12,000.00
CLASS D - DEMOLITION AND SITE CLE	ARANCE	E	\$	3,285.00
CLASS E - EARTHWORKS			\$	12,877.00
CLASS F - INSITU CONCRETE			\$	21,725.00
CLASS G - CONCRETE ANCILLERIES			\$	5,027.40
CLASS M - STRUCTURAL METALWORK			\$	801,131.91
CLASS N - MISCELLANEOUS METALWO	ORK		\$	154,540.00
CLASS O - TIMBER			\$	2,098.75
CLASS W - WATERPROOFING			\$	24,896.00
CLASS X - MISCELLANEOUS WORK			\$	49,647.56
CLASS Z - SIMPLE BUILDING WORKS			\$	971,041.18
ADDITIONAL COST			\$	651,200.00
GST EXCLUSIVE AMOUNT			\$	3,262,016.51
Adjustment from Rawlinson 2022 to 2023	@ 10%		\$	3,588,218.16
ESTIMATED GST PAYABLE (10%)			\$	3,947,039.98
TOTAL OF COST			\$	3,947,039.98
*All Bill of Quantities prepared in accordance with Civil Engineering Standard Method of Measurement 4. (Institute of Civil Engineers)				

- \$3.95 million for the building, excluding contingency, markup, and overhead.
- A contingency factor of 2.5% and a markup of 15% was used by JIC consultants.
- The inclusion of these factors resulted in a final price of \$4.65 million (10% GST included).
- The detailed cost estimates for all tasks involved in the proiect were compiled into a payment prediction schedule representing potential payments for work planned.

S CURVE




Figure 8: S - Curve

Tasks	Activity	Du	uration (wks)		Total cost	We	ekly cost	Weight
A - barge	General items & Site Establishment		1.5	\$	402,547	\$	268,364	12.34%
B-G	Footing Construction		7	\$	54,914	\$	7,845	1.68%
M - Z + Barge +	Installation of Services		1.8	\$	329,359	\$	182,977	10.10%
Additional cost -	Ground Floor Installation		5.5	\$	1,006,376	\$	182,977	30.85%
\$5,000	Module Installation		8	\$	1,463,820	\$	182,977	44.87%
\$5000	Demobilisation and Handover		1	\$	5,000	\$	5,000	0.15%
	Project Cost	\$	3,262,017					
	Adjustment from 2022 to 2023 @ 10%	\$	3,588,218.16	Week	ly expenditure			
	Markup & Contingency @17.5%	\$	4,216,156.34	Cumulative expenditure				
	GST 10%	\$	421,615.63	Adjusted from 2022 to 2023 @ 10%				
	Total Price	\$	4,637,771.97	Adjusted Cumulative Expenditure				
				Incom	ne assume		17.5%	
				Cumu	lative income			
				Reten	tion		10%	
				Net P	ayment			
				Accun	nulated paymer	nt		

ENGINEERS REPORT

SCHEDULE PROJECT TIME FRAME

Task	Days
Site possession	1
Removal of debris and vegetation	1
Site clearing and levelling	0.5
Installation of temporary facilities (sire office, ablutions, etc.)	5
Excavation for foundations and services	7
Installation of formwork and reinforcement	3
Pouring of concrete	2
Curing of concrete	23
Connection of ground floor columns to foundation	13.5
Connection of beams and bracing to columns - ground floor	6
Transportation of modules to site	8
Placement and stacking of modules using a crane (time inclusive of bolting)	32
Site clean up and waste disposal	1
Landscaping and final touches	2
Pedal and Flipper in operation. Handover to client for maintenance, inclusive of site inspections	1
TOTAL	106 days

GANNT CHART

